

# Testo 400 Universal IAQ Instrument NEBB Certified Probe Listing

Which probes meet the NEBB instrument requirements?



| Probe  | Part Number                                | Function                      | Discipline              |
|--|--|-------------------------------|-------------------------|
| Testo 400<br>Internal differential pressure sensor | 0560 0400                                  | Air Pressure                  | TAB, BSC, RCx, BET, CPT |
| Hot wire probe                                     | Bluetooth - 0635 1571<br>Wired - 0635 1572 | Air Velocity                  | TAB, BSC, RCx, BET, CPT |
| 4" Vane Anemometer probe                           | Bluetooth - 0635 9431<br>Wired - 0635 9432 | Air Velocity                  | TAB, BSC, RCx, BET, CPT |
| 0.6" Vane Anemometer probe (>=1,000 fpm)           | Bluetooth - 0635 9571<br>Wired - 0635 9572 | Air Velocity                  | TAB, BSC, RCx, BET, CPT |
| Humidity probe                                     | Bluetooth - 0636 9731<br>Wired - 0636 9732 | Humidity                      | TAB, BSC, RCx, BET, CPT |
| High precision humidity                            | Bluetooth - 0636 9771<br>Wired - 0636 9772 | Humidity                      | TAB, BSC, RCx, BET, CPT |
| NTC and Thermocouple temperature probes            | All Probes                                 | Air Meter (Temperature)       | TAB, BSC, RCx, BET, CPT |
| NTC and Thermocouple temperature probes            | All Probes                                 | Contact Meter (Temperature)   | TAB, BSC, RCx, CPT      |
| NTC and Thermocouple temperature probes            | All Probes                                 | Immersion Meter (Temperature) | TAB, BSC, RCx, CPT      |
| Lux probe  | Wired - 0635 0551                          | Light Level Measurement       | RCx                     |



#### Discipline Key:

TAB – Testing, Adjusting and Balance  
 BSC – Building Systems Commissioning for New Construction  
 RCx – Technical Retro-Commissioning for existing buildings  
 BET – Building Enclosure Testing  
 CPT – Cleanroom Performance Testing

